

Road Name	Improvement of Kamwerini - Kiunga Primary School - Kwa Kireru to Main Road and Mirambaikamba SDA - Kandimu Primary School Road						
Road ID	G60340/ G60441						
Length (KM)	12.5						
Scope of Work	Site clearance, Culverts and drainage works, Grading and Spot graveling						
Activity Code	Activity Descriptions	Works Category	Maintenance Method	Unit	Planned Quantity	Planned Rate	Amount (Ksh)
01-50-026	Allow a prime cost sum for Annual Road Condition Surveys (ARICS)	RM	LB-MB	PC SUM	1	150,000.00	150,000.00
01-50-027	Include % of Prime cost in item 01-50-026 for contractor's overhead and profit.		LB-MB		1	10.00	15,000.00
01-60-004	Quality Control Test and Survey		LB-MB	PC SUM	1	45,000.00	45,000.00
01-60-005	Include % of Prime cost in item 01-60-004 for contractor's overhead and profit.		LB-MB		1	10.00	4,500.00
01-60-006	Provide and erect publicity signboards as guided by engineer-standard drawings to be provided		LB-MB	No.	1	35,000.00	35,000.00
01-80-012	Allow PC sum for site staff transport		LB-MB	PC SUM	1	75,000.00	75,000.00
04-50-002	Clear site on road reserve mechanically by removal of trees, hedges, bushes, vegetation and other deleterious materials including filling of minor gulleys as directed by the Engineer using wheel shovel		MB	M ²	45,000.0		
08-60-026	Provide, lay and join 900mm inner dia concrete pipes.		LB-MB	LM	66.0		
08-60-019	C20/20 for culvert end structures including steel fabric mesh A142		LB-MB	M ³	40.0		
10-60-002	Gravelling without watering or compaction		MB	M ³	270.0		
10-60-002	Heavy grading without watering or compaction as directed by the engineer including cutting of backslopes		MB	M ²	87,500.0		
					Sub-Total 1		
					Add 16% VAT		

Activity Code	Activity Descriptions	Works Category	Maintenance Method	Unit	Planned Quantity	Planned Rate	Amount (Ksh)
					Total		