

Road Name	Construction of Mutendea River Drift (90metres) along Misungwani - Mutendea River - Kwa Mbaa Nzuna - Mukuna- Mukuyu Road						
Road ID	P30_Kitui						
Length (KM)	0.09						
Scope of Work	90m drift						
Activity Code	Activity Descriptions	Works Category	Maintenance Method	Unit	Quantity	Rate	Amount (Ksh)
01-50-026	Allow a prime cost sum for Annual Road Codition Surveys (ARICS)	SI	LB-MB	PC Sum	1.00	200,000	200,000.00
01-50-027	Include % of Prime cost in item 01-50-026 for contractor's overhead and profit.			%	1.00	10.00	20,000.00
01-60-004	Quality Control Test and Surveys		LB-MB	PC Sum	1.00	100,000.00	100,000.00
01-60-005	Include % of Prime cost in item 01-60-004 for contractor's overhead and profit.			%	15.00	10.00	10,000.00
01-60-006	Provide and erect publicity signboards as guided by engineer-standard drawings tobe provided		LB-MB	No.	1.00	40,000.00	40,000.00
01-80-012	Allow PC sum for site staff transport		LB-MB	PC Sum	1.00	50,000.00	50,000.00
	Include % of Prime cost in item 01-60-012 for contractor's overhead and profit.			%	1.00		500.00
07-50-001	Excavate for structure in soft material			M3	658		
07-50-002	Excavate for structure in hard material			M3	273		
07-50-006	Selected granular fill material			M3	292		
08-70-004	provide and place gabion installation			M2	990.00		
08-70-005	provide and place rock fill to gabions			M3	180.00		
09-50-01	Construct and maintain 3m wide deviation			KM	0.20		
17-60-001	Provide, place and compact C15/20 concrete for blinding			M3	30.30		
17-60-002	Provide, place and compact C 25/20 concrete to walls, bases and to top slab			M3	305.80		
17-60-003	Vertical formwork class F2 finish			M2	1,220.00		

Activity Code	Activity Descriptions	Works Category	Maintenance Method	Unit	Quantity	Rate	Amount (Ksh)
17-60-005	Provide, cut, bend and fix into position high yield reinforcement			TON	13.80		
20-50-004	Edge marker posts			NO.	4.00		
					<b>Sub-Total 1</b>		
						Add 16% VAT	
					<b>Total</b>		