Road Name:	**Ukasi-Sosoma-Egamba-Dam Side**					
Road ID:	D1214, F2095, G30669					
Length:	87.5km					
Scope of Work:	Site Clearance, Earthworks,Grading and Gravelling Works, Culvert and Drainage Works					
Activity Code	**Description**	**Technology**	**Unit**	**Quantity**	**Rate (Kshs)**	**Amount (Kshs)**
01-60-005	Publicity Sign Board	LB-MB	No.	1	40,000.00	40,000.00
01-60-0004	Quality control tests and surveys	LB-MB	PC SUM	1	40,000.00	40,000.00
01-60-040	Extra over 01-60-004 for overheads and profits	LB-MB	%	1	10.0	4,000.00
01-80-012	Allow a prime cost sum of ksh.75,000 for supervision team transport espenses	LB-MB	PC SUM	1	75,000.00	75,000.00
01-80-012	Extra over 01-80-012 for overheads and profits	LB-MB	%	1	10%	7,500.00
01-80-026	Allow a prime cost sum for Annual Road Codition Surveys (ARICS)	LB-MB	PC SUM	1	150,000.00	150,000.00
01-80-027	Extra over 01-80-026 for profit and overheards	LB-MB	%	1	10	15,000.00
04-50-003	Light bush clearing	LB	M^2	87,500.00		
05-50-006	Fill in soft material without compaction	LB	M^3	2,700		
08-60-024	Provide,lay and joint pipe culverts of 600mm diameter with surround	LB-MB	MT	18		
08-60-026	Provide,lay and joint pipe culverts of 900mm diameter with surround	LB-MB	MT	54		
08-70-006	Construction of scourchecks (Concrete)	LB	No	50		
10-50-001	Light grading without watering or compaction	MB	M^2	525,000.00		
10-60-001a	Gravelling without watering and compaction	MB	M^3	1800		

Road Name:	**Ukasi-Sosoma-Egamba-Dam Side**					
Road ID:	D1214, F2095, G30669					
Length:	87.5km					
Scope of Work:	Site Clearance, Earthworks,Grading and Gravelling Works, Culvert and Drainage Works					
Activity Code	**Description**	**Technology**	**Unit**	**Quantity**	**Rate (Kshs)**	**Amount (Kshs)**
				Sub-Total 1		
			Add 0.03% Procurement Capacity Building Levy			
				Add 16% VAT		
				Total		