Road Name:	Mangoloma Drift along Good Sherperd - Kyanika Road					
Road ID:	G41234					
Length:	100m drift					
Scope of Work:	Excavation & Filling for Structures, Culverts & Drainage Works, Concrete for Major Structures					
Activity Code	**Description**	**Technology**	**Unit**	**Quantity**	**Rate (Kshs)**	**Amount (Kshs)**
01-60-005	Publicity Sign Board	LB-MB	No.	1	40,000.00	40,000.00
01-60-0004	Quality control tests and surveys	LB-MB	PC SUM	1	40,000.00	40,000.00
01-60-040	Extra over 01-60-004 for overheads and profits	LB-MB	%	1	10.0	4,000.00
01-80-012	Allow a prime cost sum of ksh.50000 for supervision team transport espenses	LB-MB	PC SUM	1	50,000.00	50,000.00
01-80-012	Extra over 01-80-012 for overheads and profits	LB-MB	%	1	10%	5,000.00
01-80-026	Allow a prime cost sum for Annual Road Codition Surveys (ARICS)	LB-MB	PC SUM	1	150,000.00	150,000.00
01-80-027	Extra over 01-80-026 for profit and overheards	LB-MB	%	1	10	15,000.00
07-50-001	Excavate for structure in soft material	LB	M^3	678		
07-50-002	Excavate for structure in hard material	LB	M^3	60		
07-50-006	Selected granular fill material	LB-MB	M^3	330		
08-60-019	Provide, place and compact C15/20 concrete for blinding	LB	M^3	33.86		
08-60-036	Provide, place and compact C25/20 concrete	LB	M^3	206		
08-070-004	Gabbion Installation	LB	M^2	550		
08-070-005	Provide and place Rockfill to Gabbions	LB	M^3	100		
09-50-003	construct and maintain 3m wide deviation	MB	KM	0.2		
17-50-005	Provide,cut bend and fix into position high yield reinforcement bars	LB	Ton	9.80		

Road Name:	**Mangoloma Drift along Good Sherperd - Kyanika Road**					
Road ID:	G41234					
Length:	100m drift					
Scope of Work:	Excavation & Filling for Structures, Culverts & Drainage Works, Concrete for Major Structures					
Activity Code	**Description**	**Technology**	**Unit**	**Quantity**	**Rate (Kshs)**	**Amount (Kshs)**
17-60-003	Vertical formwork class F1 finish	LB	M^2	636		
				Sub-Total 1		
			Add 0.03% Procurement Capacity Building Levy			
				Add 16% VAT		
				Total		