Road Name:	Construction of Kwa Ilate Box Culvert					
Road ID:	G31923					
Length:	.					
Scope of Work:	Twin Box Culvert - 5mx2.5mx2no.					
Activity Code	**Description**	**Technology**	**Unit**	**Quantity**	**Rate (Kshs)**	**Amount (Kshs)**
01-50-026	Allow a prime cost sum of Kshs 200,000 for Annual Road Codition Surveys (ARICS)	LB-MB	PC Sum	1.00	200,000.00	200,000.00
01-50-027	Include % of Prime cost in item 01-50-026 for contractor's overhead and profit.		%		15.00	30,000.00
01-60-002	Clearance on completion	LB-MB	LumpSum	1.00	5,000.00	5,000.00
01-60-004	Quality Control Test and Survey	LB-MB	PC Sum	1.00	100,000.00	100,000.00
01-60-04a	Include % of Prime cost in item 01-60-004 for contractor's overhead and profit.		%		0.15	15,000.00
01-60-005	Provide and erect publicity signboards	LB-MB	No	2.00		
01-60-006	Drinking Water	LB-MB	Month	4.00		
01-60-007	Provision of Site Sanitary Facilities	LB-MB	Month	4.00		
05-50-004	Cut to fill in hard materials with compaction	MB	cm	600.00		
07-50-002	Excavation & spread in soft material & compact	MB	m3	200.00		
07-50-003	Excavation & spread in hard material & compact	MB	m3	400.00		
07-50-004	Excavation to level & compaction	MB	m3	200.00		
07-50-005	Spreading & compaction camber formation	MB	m3	450.00		
08-70-004	Provide and place gabions	LB	No.	400.00		
08-70-005	Provide and place rockfill to gabions	LB	m3	800.00		
17-60-001	Provide, place and compact C15/20 for blinding	LB	m3	100.00		
17-60-002	Provide, place and compact C25/20 for walls, base, top slab, headwalls and wingwalls	LB-MB	m3	136.00		
17-60-003	Formwork Class F2 finish	LB	m2	400.00		
17-60-005	Provide, cut, bend and fix into position high yield reinforcement	LB	Ton	9.80		
20-50-004	Provide and place new flex beams guardrails complete with steel flex beam guard rail posts, nuts bolts and fittings as directed by the Engineer. To include 50mm GI pipe handrail	LB-MB	MT	128.00		

Road Name:	**Construction of Kwa Ilate Box Culvert**					
Road ID:	G31923					
Length:	.					
Scope of Work:	Twin Box Culvert - 5mx2.5mx2no.					
Activity Code	**Description**	**Technology**	**Unit**	**Quantity**	**Rate (Kshs)**	**Amount (Kshs)**
20-50-005	Erection of Traffic Signs	LB	No	4.00		
				Sub-Total 1		
			Add 0.03% Procurement Capacity Building Levy			
				Add 16% VAT		
				Total		