Road Name:	Kwa Mukwa - Vinda - Makaani - Ndivuni					
Road ID:	L3_Kitui, F2020					
Length:	9.8km					
Scope of Work:	Site Clearance, Excavation & Filling for Structures, Culvert and Drainage Works, Grading and Concrete Works					
Activity Code	**Description**	**Technology**	**Unit**	**Quantity**	**Rate (Kshs)**	**Amount (Kshs)**
01-60-005	Publicity Sign Boards	LB-MB	No.	2.00	40,000.00	80,000.00
01-80-010	Allow a prime cost of sum for material testing and Surveys as directed by the Engineer	LB-MB	PC SUM	1.00	60,000.00	60,000.00
01-80-026	Allow a prime cost sum of Ksh.200,000 for Annual Road Codition Surveys (ARICS)	LB-MB	PC SUM	1.00	200,000.00	200,000.00
01-80-027	Extra over 01-80-026 for profits and overheads	LB-MB	%		15.00	30,000.00
01-80-028	Allow a prime cost sum for site staff transport	LB-MB	PC SUM	1.00	80,000.00	80,000.00
01-80-029	Extra over 01-80-028 for profits and overheads		%		15.00	12,000.00
04-50-002	Heavy bush clearing	LB	M2	17,600.00		
04-50-003	Light bush clearing	LB	M2	10,800.00		
07-50-001	Excavate for structure in soft material	LB	M3	37.20		
07-50-002	Excavate for structure in hard material	LB	M3	104.16		
07-50-006	Selected granular fill material	LB	M3	60.00		
08-60-025	Culvert Installation 600 mm with surround	LB-MB	M	18.00		
08-60-027	Culvert Installation 900 mm with surround	LB-MB	M	18.00		
08-60-035	provide place and compact class 15/20 concrete	LB-MB	M3	98.00		

Road Name:	**Kwa Mukwa - Vinda - Makaani - Ndivuni**					
Road ID:	L3_Kitui, F2020					
Length:	9.8km					
Scope of Work:	Site Clearance, Excavation & Filling for Structures, Culvert and Drainage Works, Grading and Concrete Works					
Activity Code	**Description**	**Technology**	**Unit**	**Quantity**	**Rate (Kshs)**	**Amount (Kshs)**
08-60-036	provide place and compact class 20/20 concrete	LB-MB	M3	294.00		
08-60-037	provide and place A142 fabric mesh rfcmnt	LB-MB	M2	1,960.00		
09-50-01	Construct and maintain 3m wide deviation	MB	KM	0.60		
10-50-002	Heavy grading WITHOUT watering and compaction including formation of ditches and side slopes	MB	M2	58,800.00		
17-60-001	Provide, place and compact C15/20 concrete for blinding	MB-LB	M3	8.13		
17-60-002	Provide, place and compact C 20/20 concrete to walls, bases and to top slab	MB-LB	M3	18.00		
17-60-003	Vertical formwork class F2 finish	MB-LB	M2	60.00		
17-60-005	Provide, cut, bend and fix into fix into position high yield reinforcement	MB-LB	TON	3.00		
20-50-004	Edge marker posts	LB	No.	4.00		
				Sub-Total 1		
			Add 0.03% Procurement Capacity Building Levy			
				Add 16% VAT		
				Total		