Road Name:	**Manyenyoni - Wii - Wikililye B61Katulani Road**					
Road ID:	P12_Kitui, F1947, P144_Kitui					
Length:	8.4km					
Scope of Work:	Site clearance, Culverts and Drainage Works, Concrete slab,Grading					
Activity Code	**Description**	**Technology**	**Unit**	**Quantity**	**Rate (Kshs)**	**Amount (Kshs)**
01-60-005	Publicity Sign Boards	LB-MB	NO.	1.00	40,000.00	40,000.00
01-80-010	Allow a prime cost of sum for material testing as directed by the Engineer	LB-MB	PC SUM	1.00	50,000.00	50,000.00
01-80-026	Allow a prime cost sum of Ksh. 150,000 for Annual Road Codition Surveys (ARICS)	LB-MB	PC SUM	1.00	150,000.00	150,000.00
01-80-027	Extra over 01-80-026 for profits and overheads	LB-MB	%		15.00	22,500.00
01-80-028	Allow a prime cost sum for site staff transport	MB	PC SUM	1.00	100,000.00	100,000.00
01-80-029	Extra over 01-80-028 for profits and overheads		%		15.00	15,000.00
04-60-001	Road widening	MB	M^2	20,000.00		
04-50-003	Heavy bush clearing	MB	M^2	13,600.00		
07-50-001	Excavate for structure in soft material	LB	M^3	25.20		
07-50-002	Excavate for structure in hard material	MB	M^3	70.56		
08-60-025	Culvert Installation 600 mm with surround	LB-MB	M	12.00		
08-60-027	Culvert Installation 900 mm with surround	LB-MB	M	24.00		
08-60-035	provide place and compact class 15/20 concrete	LB	M^3	56.00		
08-60-036	provide place and compact class 20/20 concrete	LB-,MB	M^3	168.00		

Road Name:	**Manyenyoni - Wii - Wikililye B61Katulani Road**					
Road ID:	P12_Kitui, F1947, P144_Kitui					
Length:	8.4km					
Scope of Work:	Site clearance, Culverts and Drainage Works, Concrete slab,Grading					
Activity Code	**Description**	**Technology**	**Unit**	**Quantity**	**Rate (Kshs)**	**Amount (Kshs)**
08-60-037	provide and place A142 fabric mesh rfcmnt	LB	M^2	1,120.00		
08-70-004	provide and place gabion installation	LB	NO.	30.00		
08-70-005	provide and place rock fill to gabions	LB	M^3	60.00		
09-50-01	Construct and maintain 3m wide deviation		KM	0.30		
10-50-002	Heavy grading WITHOUT watering and compaction including formation of ditches and side slopes	MB	M^2	50,400.00		
10-50-001	Gravel patching without watering or compaction	MB	M^3	450.00		
17-60-003	Vertical formwork class F2 finish	LB	M^2	20.00		
				Sub-Total 1		
			Add 0.03% Procurement Capacity Building Levy			
				Add 16% VAT		
				Total		