Road Name:	**Kanyangi - Ndovoini - Nzambia**					
Road ID:	F1712					
Length:	7.6km					
Scope of Work:	Concrete Slabs, Grading and Graveling					
Activity Code	**Description**	**Technology**	**Unit**	**Quantity**	**Rate (Kshs)**	**Amount (Kshs)**
01-60-005	Publicity Sign Boards	LB-MB	No.	1.00	40,000.00	40,000.00
01-80-010	Allow a prime cost of sum for material testing as directed by the Engineer	LB-MB	PC SUM	1.00	30,000.00	30,000.00
01-80-026	Allow a prime cost sum of Ksh.125,000 for Annual Road Codition Surveys (ARICS)	LB-MB	PC SUM	1.00	125,000.00	125,000.00
01-80-027	Extra over 01-80-026 for profits and overheads	LB-MB	%	1.00	10.00	18,750.00
01-80-012	Allow a prime cost of Kshs. 50,000 for site supervision staff transport expenses		PC SUM	1.00	50,000.00	50,000.00
01-80-013	Extra over 01-80-012 for profits and overheads	LB-MB	%	1.00	10.00	7,500.00
07-50-001	Excavate for structure in soft material	LB	M3	316.80		
07-50-002	Excavate for structure in hard material	MB	M3	52.80		
08-60-027	Culvert Installation 600 mm with surround	LB-MB	M	48.00		
08-60-036	provide place and compact class 20/25 concrete	LB-MB	M3	184.00		
08-60-037	provide and place A142 fabric mesh rfcmnt	LB	M2	1,200.00		
10-50-002	Heavy grading WITHOUT watering and compaction including formation of ditches and side slopes .	MB	M2	45,600.00		
10-60-001	Gravel patching without watering and compaction	MB	M3	555.00		
				Sub-Total 1		
			Add 0.03% Procurement Capacity Building Levy			
				Add 16% VAT		

Road Name:	**Kanyangi - Ndovoini - Nzambia**					
Road ID:	F1712					
Length:	7.6km					
Scope of Work:	Concrete Slabs, Grading and Graveling					
				Total		